



**Addendum No. 7
March 19, 2019**

Project: Lake Area Technical Institute
Prairie Lakes Healthcare Center of Learning
Watertown, South Dakota

Architect: CO-OP Architecture

SCOPE OF THIS ADDENDUM:

To all bidders and all others to whom drawings and specifications have been issued by CO-OP Architecture.

Acknowledge receipt of this addendum by listing its number and date in the bidders Form of Proposal. Failure to do so may subject bidder to disqualification. This Addendum forms a part of the Contract Documents.

It modifies them as follows:

GENERAL ITEMS:

1. See attached plan holders list.
2. Any documents provided for the project including meeting notes, addendums, etc., will be made available to access in the dropbox folder throughout the bidding process.
3. This is the final addendum for this project for bidding purposes. Addendum #6 was previously noted as the last addendum however this Addendum #7 is the last and final Addendum.

REVISIONS TO DRAWINGS:

1. DRAWING SHEET A1-7, DETAIL 11.
 - a. Delete Keynote 9.21 at horizontal window mullion aligned with top of casework back splash. Add to provide Epoxy window sill at this location to match epoxy countertops. All other windows that do not have casework installed in front of them will have a solid surface window sill as specified.
2. DRAWING SHEET A0-1, WALL TYPES 5A, 5C & 6C
 - a. All notes that refer to “3” MIN. SPRAY APPLIED INSULATION -OR- BATT INSULATION” Add the following: **(SEE SECTIONS AND DETAILS TO DETERMINE INSTALLATION LOCATION OF EACH PRODUCT)**
Clarification is to make aware the spray applied insulation is expected at all exterior walls and that Batt Insulation is acceptable at locations such as parapets were coordination of spray application is not feasible.
3. DRAWING SHEET RM9-1, SK-2
Please note that sink SK-2 will be provided per Specification Section 123553.19 2.2 D.

REVISIONS TO SPECIFICATIONS:

1. Section 075323 2.07 A.

- a. Add Note: Rough carpentry shall be provided by Section 061000. Misc. carpentry may still be required per this section as a result of tying into the existing building.
- 2. Section 081416 1.02
 - a. Delete Item D.

Note: All wood doors to be provided with factory finish.

END OF ADDENDUM-7